

August 15, 2008

Mr. John Johnson, Selectman  
Town of Edgecomb  
P.O. Box 139  
Edgecomb, ME 04556-01396

RE: Proposal Task Order for Review of Edgecomb Development Proposed Sewer  
Connection Phase 2B and Inspection Services

Dear John:

As you requested, we are presenting you this task order to assist the Town of Edgecomb with the review and inspection of the proposed Phase 2B development by Edgecomb Development LLC. This task order will continue our ongoing effort to provide the Town with the planning and engineering assistance necessary to ensure the development of a sewer utility management system that provides the Town (Davis Island) with long term reliable wastewater collection. Our proposed scope of work includes:

1. Complete a review of the wastewater transport system for Phase 2B of the Edgecomb Development along Eddy Road in Edgecomb. The system consists of approximately 800 feet of gravity sewer and force main, service connections, and 7 manholes. This review of proposed development plans is to ensure that Edgecomb Development LLC had designed the system according to the Town's standards (ordinances) so the Town will have a reliable collection system in the future.
2. Evaluate the capacity of the transport system going through the development with respect to extending the sewer service to include Fort Road.
3. Review proposed maximum daily sewage flow and resulting impact fee for connection to the sewer utility.
4. Estimate the Town of Edgecomb's reserve flow capacity with respect to the Interlocal Agreement with Wiscasset.
5. Provide one day of onsite inspection oversight to observe pressure tests, vacuum tests, and mandrel tests to ensure the construction/installation of the transport system is according to the drawings and specifications. We assumed that the Contractor can test the entire system in one day.
6. Meet with Town to present/discuss results of this scope of work.

This project is a task order subject to the Terms and Conditions and Schedule of Payment of the General Services Agreement with the Town dated August 23, 2007. This task order outlines the tasks necessary to complete this work and an estimate of the engineering fees and associated costs. We anticipate completing the majority of the work in several weeks. More time may be necessary to complete the inspection portion of the work if construction is not completed within this time. We anticipate that this project will require a maximum of 60 engineering and meeting hours and a budget reserve of \$6,780 including expenses. We will complete this work on a time and materials basis.

Please review this information to assure that it matches your expectations. If you have any questions or have suggestions for improvement, feel free to call me at 1-800-426-4262. If this contract meets your needs, please sign both copies on the line provided below and return one copy to this office for my records.



Very truly yours,

WOODARD & CURRAN INC.



Kyle M. Coolidge, P.E.  
Project Engineer

KMC  
203592.07

Offered this 15 Day of August, 2008

Accepted this \_\_\_\_\_ Day of August, 2008

By

A handwritten signature in dark ink, appearing to read "Kyle M. Coolidge", is written over a solid horizontal line.

Woodard & Curran, Inc.

By \_\_\_\_\_

Town of Edgecomb